

Worksite: Squamish Terminals	Approved By: H&S Committee	Date Issued: November 27, 2019	Full Procedure reference: PRO-029, version 1.0
--	--------------------------------------	--	--

Key Site Safety Requirements:	Personal Protective Equipment (PPE)
<ul style="list-style-type: none"> • Wear required PPE • Attend Tool Box talk - mandatory • Site Speed Limits 20km on dock, 10km in sheds • Seatbelts mandatory • No use of electronic devices while in active working areas • No smoking on site (designated area only) • Drug and Alcohol use strictly prohibited 	<ul style="list-style-type: none"> • Hi-viz Vest • Safety Boots (6") • Type 2 Hard Hat (while on vessel; under boom; working with reach stacker; under raised forks) • Eye protection, hearing protection, gloves - recommended • Dust mask – if needed

Job Hazards Present:
<ul style="list-style-type: none"> • Slips, Trips, Falls on slippery / uneven surfaces • Pedestrians exposure to being struck by site traffic • Site vehicles / materials handling equipment striking other vehicles or stationary obstacles / equipment • Falling objects (equipment, cargo, debris, broken equipment, tools) – risk of being struck or crushed • Falling container - risk of being struck or crushed • Working under raised Reachstacker – crushing injuries, overhead hazards • Materials handling equipment - unstable load – tipping/rolling – whiplash, jarring, crushing injuries to driver • Materials handling equipment - unstable load – tipping/rolling – crushing injuries to pedestrians • Pinch Points • Sharp edges / slivers / cuts / jagers • Exposure to elements (wind, sunburn, heat index, cold, dust)

Procedure - Container Delivery to Truck
--

<ol style="list-style-type: none"> 1) Management provides Foreman with location of start (a "section"). 2) Crew is dispatched to section where the foreman will discuss operational plan with crew to ensure Longshore understand operation, safety and PPE. 3) Reachstacker driver lifts head above container, the spreader is lowered on top of the container, it locks the four corners (corner castings) by a twist lock mechanism 4) Reachstacker Driver lifts a container from the pile and moves to truck location on site. 5) The Reachstacker driver lifts the container above the trailer, lowers the head and sets the container onto the trailer 6) Reachstacker driver releases the spreader and backs away 7) Truck driver is responsible for securing the container to the trailer. <p>Caution:</p> <ul style="list-style-type: none"> • Truck driver must not be securing the container while the Reachstacker is operating in the vicinity • The Foreman, Labourer, Checker and Truck Driver must not stand at the side of the truck while it's being loaded. • If direction has to be given to the Reachstacker Operator it must be done from a safe position.

Container Delivery to Truck

